



SB Humane Solar Microgrid For EPC & PPA consideration

Bryan Murray

Senior Engineer

757-774-2530 mobile

bryan@clean-coalition.org

Craig Lewis

Executive Director

650-796-2353 mobile

craig@clean-coalition.org

Gregory Young

Program Manager

805-350-2931 mobile

gregory@clean-coalition.org

Key components of the SB Humane Solar Microgrid reference design (proposers can meet or exceed)

Solar system reference design:

- 339 kWdc configured in various rooftop and solar canopy configurations.
 - The rooftop configurations are mounted on angled roofs facing various directions.
 - The solar parking canopies are facing Southwest and West.
- 548,145 kWh of annual solar production (1,620 kWh/kWdc).
- 771 solar panels in total of JA Solar 395 Wdc and 540 W bifacial panels in landscape or portrait orientation, whichever optimally fits the roof or parking canopy space; or equivalent.

Battery Energy Storage System (BESS) reference design:

- 326 kW & 1,305 kWh Tesla Megapack; or equivalent.

Fossil fuel generator

- 350 kW Generac with DeepSea 8610 MKII genset controller; or equivalent.

Microgrid Controller:


- Tesla, Ageto, or equivalent.

Load Management:

- Shunt-trip breakers controlled by Ageto, Eaton, or equivalent.


Electric Vehicle Charging Infrastructure:

- 22 Level-2 EV charging ports (minimum of 7 kW of simultaneous power capacity) to be sited under the solar parking canopies (12 under the northern canopy and 10 under the eastern canopy) and designed to meet the Solar Microgrid operational requirements.



The solar system design shown in the image above is based on an outdated roof plan. Proposers should create their own solar system design based on the updated roof plans per slide 12.

Reference solar layout (based on an outdated roof plan)



SB Humane
 5399 Overpass Rd, Goleta, CA

- Service Meter
- MSB** Main Service Switchboard 1600A, 480/277V, 3PH 4W
- G** 350 kW Generac diesel generator
- 22 potential level-2 EV ports (dual ports)
- 326 kW/1,305 kWh BESS location

Total Solar Siting Potential: 339 kW

- Total Annual Solar Generation: 548,145 kWh
- 41% NZE of Master Load Profile
- 32% NZE of Baseline Load Profile

C-1	63.2 kW Solar Parking Canopy
C-2	63.2 kW Solar Parking Canopy
R-1	22.1 kW Service Bldg I rooftop solar
R-2	59.3 kW Dog Bldg A rooftop solar
R-3	10.3 kW Intake Bldg F rooftop solar
R-4	15.4 kW Cat & Rabbit Bldg B rooftop solar
R-5	75.4 kW Clinic Bldg C rooftop solar
R-6	29.6 kW Admin & Education Bldg D & E rooftop solar

Total Annual Loads:

- Baseline Load Profile: 1,341,232 kWh
- EV Load Profile: 368,879 kWh
- Master Load Profile: 1,710,111 kWh
- Critical Load Profile: 872,988 kWh

Critical Loads: Buildings A, C, F, & H

Load Profiles

Load profiles and rate schedules

The [Aggregated Profiles Spreadsheet](#) contains annual profiles in 15-minute intervals for:

1. Baseline Load Profile
2. Adjustments Load Profile (22 EV Charging Stations)
3. Master Load Profile
4. Critical Load Profile
5. Solar Generation Profile (from the reference design)

SB Humane Load and Billing Details										
Profile Type	Annual Load and Demand Values				Pre-Solar SCE & CCCE Billing Details			Post Solar Microgrid SCE & CCCE Billing Details		
	Total Annual Load (kWh)	Peak Demand (kW)	Average Demand (kW)	Minimum Demand (kW)	SCE & CCCE Rate Schedule	CCCE Rate Schedule	SCE Service Rating (V)	SCE & CCCE Rate Schedule	CCCE Rate Schedule	SCE Service Rating (V)
Baseline Load Profile	1,341,232	363	153	43	TOU-GS-3D	3Cchoice	480	TOU-GS-3E	3Cchoice	480
22 EV Charging Stations	368,879	154	42	0	-	-	-	-	-	-
Master Load Profile	1,710,111	517	195	43	TOU-GS-3D	3Cchoice	480	TOU-GS-3E	3Cchoice	480
Critical Load Profile (Buildings A, C, F & H)	872,988	256	100	25	-	-	-	-	-	-

TOU-GS-3D has a expected monthly peak demand of 200 kW through 500 kW. SB Humane’s peak demand will be reduced with solar and not exceed this peak demand threshold.

Building phases

Site overview

SB Humane Campus

- 9 Buildings (see slide 26)
 - 4 critical
 - 5 non-critical
- 22 Level-2 EV charging ports
 - 10 ports on one circuit.
 - 12 ports on another circuit.

Two-Phase Construction

- Phase 1: Oct 2024 - Dec 2025
- Phase 2: Dec 2025 - Nov 2027
 - **Solar Microgrid all in Phase 2**

Solar Microgrid & diesel generator from reference design


- Solar: 339kWh
- BESS: 326kW & 1,305kWh
- Fossil fuel generator: 350kW

Site progress set

Updated PV Array 2/8/24

Name of Building	Number of Panels	Space Footage
A. City Hall	145	1,028.00 SF
B. Cal Adventure	35	185.00 SF
C. Clinic	165	1,038.00 SF
Cell Station & Storage	52	1,700.00 SF
E. Exhibit	35	141.00 SF
F. Service	43	165.00 SF
Total Roof Mounted	475	6,862.00 SF
Clear Roof Parking Area	162	1,446.25 SF
Clear Court Parking Area	133	2,214.75 SF
Total Inst. Parking	295	3,661.00 SF

(Note: Selected Solar Panels 20'x10' with a 2' spacing between panels. About 200 - 250 kWh of space with this layout.)



Site Roof Plan Keynote Legend

Keynote	Description
1	Phase 1 Construction Area
2	Phase 2 Construction Area
3	Clear Roof Parking Area
4	Clear Court Parking Area
5	Roof Mounted Solar Panel Array
6	Roof Mounted Solar Panel Array (20'x10')
7	Roof Mounted Solar Panel Array (10'x20')
8	Roof Mounted Solar Panel Array (5'x10')
9	Roof Mounted Solar Panel Array (10'x5')
10	Roof Mounted Solar Panel Array (5'x5')
11	Roof Mounted Solar Panel Array (2'x10')
12	Roof Mounted Solar Panel Array (10'x2')
13	Roof Mounted Solar Panel Array (2'x5')
14	Roof Mounted Solar Panel Array (5'x2')
15	Roof Mounted Solar Panel Array (1'x10')
16	Roof Mounted Solar Panel Array (10'x1')
17	Roof Mounted Solar Panel Array (1'x5')
18	Roof Mounted Solar Panel Array (5'x1')
19	Roof Mounted Solar Panel Array (1'x2')
20	Roof Mounted Solar Panel Array (2'x1')

DMHA
ARCHITECTURE + INTERIOR DESIGN

110 Clark Center, Chelsea #102
Santa Barbara, CA 93103

805.895.7777

Santa Barbara HUMANE

SB Humane - Campus Renovation
5300 Overcrest Road
Santa Barbara, CA 93103
PROJECT #: 202301
NO. DESCRIPTION DATE


AS103.2
PHASE 2 CAMPUS ROOF & PV ARRAY PLAN

PHASE 2 SITE ROOF PLAN 01

Site progress set

PROPOSED BUILDING LEGEND

BUILDING NAME	ENCLOSED BLDG AREA (CONDITIONED)	COVERED EXTERIOR AREA (UNCONDITIONED)
A	RECEPTION & DOG ADOPTION	8,601 SF
B	CAT & RABBIT ADOPTION	2,261 SF
C	ANIMAL CLINIC	9,529 SF
D	EDUCATION BUILDING (REMODEL)	3,799 SF
E	ADMINISTRATION BUILDING	5,078 SF
F	INTAKE BUILDING	7,725 SF
G	BEHAVIOR CENTER	1,281 SF
I	SERVICE BUILDING	1,387 SF
TOTAL		39,661 SF
H	HISTORIC BECK HOUSE	1,571 SF
GRAND TOTAL		41,232 SF



Site Plan Keynote Legend

Symbol	Description
1	1'0" Vertical Parking Space
2	2'0" Vertical Parking Space
3	3'0" Vertical Parking Space
4	4'0" Vertical Parking Space
5	5'0" Vertical Parking Space
6	6'0" Vertical Parking Space
7	7'0" Vertical Parking Space
8	8'0" Vertical Parking Space
9	9'0" Vertical Parking Space
10	10'0" Vertical Parking Space
11	11'0" Vertical Parking Space
12	12'0" Vertical Parking Space
13	13'0" Vertical Parking Space
14	14'0" Vertical Parking Space
15	15'0" Vertical Parking Space
16	16'0" Vertical Parking Space
17	17'0" Vertical Parking Space
18	18'0" Vertical Parking Space
19	19'0" Vertical Parking Space
20	20'0" Vertical Parking Space
21	21'0" Vertical Parking Space
22	22'0" Vertical Parking Space
23	23'0" Vertical Parking Space
24	24'0" Vertical Parking Space
25	25'0" Vertical Parking Space
26	26'0" Vertical Parking Space
27	27'0" Vertical Parking Space
28	28'0" Vertical Parking Space
29	29'0" Vertical Parking Space
30	30'0" Vertical Parking Space
31	31'0" Vertical Parking Space
32	32'0" Vertical Parking Space
33	33'0" Vertical Parking Space
34	34'0" Vertical Parking Space
35	35'0" Vertical Parking Space
36	36'0" Vertical Parking Space
37	37'0" Vertical Parking Space
38	38'0" Vertical Parking Space
39	39'0" Vertical Parking Space
40	40'0" Vertical Parking Space
41	41'0" Vertical Parking Space
42	42'0" Vertical Parking Space
43	43'0" Vertical Parking Space
44	44'0" Vertical Parking Space
45	45'0" Vertical Parking Space
46	46'0" Vertical Parking Space
47	47'0" Vertical Parking Space
48	48'0" Vertical Parking Space
49	49'0" Vertical Parking Space
50	50'0" Vertical Parking Space
51	51'0" Vertical Parking Space
52	52'0" Vertical Parking Space
53	53'0" Vertical Parking Space
54	54'0" Vertical Parking Space
55	55'0" Vertical Parking Space
56	56'0" Vertical Parking Space
57	57'0" Vertical Parking Space
58	58'0" Vertical Parking Space
59	59'0" Vertical Parking Space
60	60'0" Vertical Parking Space
61	61'0" Vertical Parking Space
62	62'0" Vertical Parking Space
63	63'0" Vertical Parking Space
64	64'0" Vertical Parking Space
65	65'0" Vertical Parking Space
66	66'0" Vertical Parking Space
67	67'0" Vertical Parking Space
68	68'0" Vertical Parking Space
69	69'0" Vertical Parking Space
70	70'0" Vertical Parking Space
71	71'0" Vertical Parking Space
72	72'0" Vertical Parking Space
73	73'0" Vertical Parking Space
74	74'0" Vertical Parking Space
75	75'0" Vertical Parking Space
76	76'0" Vertical Parking Space
77	77'0" Vertical Parking Space
78	78'0" Vertical Parking Space
79	79'0" Vertical Parking Space
80	80'0" Vertical Parking Space
81	81'0" Vertical Parking Space
82	82'0" Vertical Parking Space
83	83'0" Vertical Parking Space
84	84'0" Vertical Parking Space
85	85'0" Vertical Parking Space
86	86'0" Vertical Parking Space
87	87'0" Vertical Parking Space
88	88'0" Vertical Parking Space
89	89'0" Vertical Parking Space
90	90'0" Vertical Parking Space
91	91'0" Vertical Parking Space
92	92'0" Vertical Parking Space
93	93'0" Vertical Parking Space
94	94'0" Vertical Parking Space
95	95'0" Vertical Parking Space
96	96'0" Vertical Parking Space
97	97'0" Vertical Parking Space
98	98'0" Vertical Parking Space
99	99'0" Vertical Parking Space
100	100'0" Vertical Parking Space

DMHA
ARCHITECTURE + INTERIOR DESIGN
600 9th St. #100
Santa Barbara, CA 93101
805.962.7177
1 N. Cady Street, Suite #102
Santa Barbara, CA 93101

Santa Barbara HUMANE

NOT FOR CONSTRUCTION

SB Humane - Campus Renovation
5206 Overpass Road
Santa Barbara, CA 93101
PROJECT #1: 30C281

NO.	DESCRIPTION	DATE
1	100% Final Design	11/15/2017
2	95% Final Design	11/15/2017
3	90% Final Design	11/15/2017
4	85% Final Design	11/15/2017
5	80% Final Design	11/15/2017
6	75% Final Design	11/15/2017
7	70% Final Design	11/15/2017
8	65% Final Design	11/15/2017
9	60% Final Design	11/15/2017
10	55% Final Design	11/15/2017
11	50% Final Design	11/15/2017
12	45% Final Design	11/15/2017
13	40% Final Design	11/15/2017
14	35% Final Design	11/15/2017
15	30% Final Design	11/15/2017
16	25% Final Design	11/15/2017
17	20% Final Design	11/15/2017
18	15% Final Design	11/15/2017
19	10% Final Design	11/15/2017
20	5% Final Design	11/15/2017

AS102.3
CAMPUS LAND USE PLAN


Campus roof plan, landscaping plan, and
reference solar design

Campus roof plan

Updated PV Array 2/8/24

Name of Building	Number of Panels	Square Footage
A. Dog Adoption	140	3,129.29 SF
B. Car Adoption	38	838.8 SF
C. Clinic	140	3,129.8 SF
DIC: Admin & Education	82	1,809.7 SF
E. Intake	38	841.1 SF
F. Service	48	105.29 SF
Total Roof Mounted	474	10,883.6 SF
Over North Parking Area	160	3,492.29 SF
Over South Parking Area	120	2,714.29 SF
Total Roof Parking	280	6,206.58 SF

(New Selected Solar Panels 39'x7' with a 2' spacing between panels)
About 240 - 250 kW of solar with this layout.



Site Roof Plan Keynote Legend

1	Roof-mounted solar panel array (indicated by grid pattern)
2	Roof-mounted solar panel array (indicated by grid pattern)
3	Roof-mounted solar panel array (indicated by grid pattern)
4	Roof-mounted solar panel array (indicated by grid pattern)
5	Roof-mounted solar panel array (indicated by grid pattern)
6	Roof-mounted solar panel array (indicated by grid pattern)
7	Roof-mounted solar panel array (indicated by grid pattern)
8	Roof-mounted solar panel array (indicated by grid pattern)
9	Roof-mounted solar panel array (indicated by grid pattern)
10	Roof-mounted solar panel array (indicated by grid pattern)

DMHA
ARCHITECTURE + INTERIOR DESIGN
805.965.7777
1 N. Calle Cesar Chavez #102
Santa Barbara, CA 93103

Santa Barbara HUMANE

NOT FOR CONSTRUCTION


SB Humane - Campus Renovation
2309 Overland Road
Goleta, CA 93111
PROJECT #: 20C381

NO.	DESCRIPTION	DATE
001	Site Plan	10/20/2023
002	Site Plan	10/20/2023
003	Site Plan	10/20/2023
004	Site Plan	10/20/2023
005	Site Plan	10/20/2023
006	Site Plan	10/20/2023
007	Site Plan	10/20/2023
008	Site Plan	10/20/2023
009	Site Plan	10/20/2023
010	Site Plan	10/20/2023

AS103.2
PHASE 2 CAMPUS ROOF & PV ARRAY PLAN

Landscaping plan

SANTA BARBARA HUMANE
PHASE 1 LANDSCAPE PLANS
 5399 OVERPASS ROAD
 GOLETA, CA 93111



SHEET INDEX

SHEET	DESCRIPTION
PHASE 1 LANDSCAPE SHEETS	
L1-100	TITLE SHEET
L1-101	TREE SPECIFICATION PLAN
L1-102	ARBOREUM REPORT
L1-103	CONSTRUCTION SITE PLAN, NOTES & SCHEDULE
L1-104	SPRINKLER WALL PLAN
L1-105	LANDSCAPE PLAN - PHASE 1
L1-106	LANDSCAPE PLAN - PHASE 2
L1-107	LANDSCAPE PLAN - PHASE 3
L1-108	PLANTING SITE PLAN - PHASE 1
L1-109	PLANTING SITE PLAN - PHASE 2
L1-110	PLANTING SITE PLAN - PHASE 3
L1-111	PLANTING DETAILS
L1-112	CONSTRUCTION DETAILS - FENCING & GATES
L1-113	CONSTRUCTION DETAILS - SIGNAGE
L1-114	PLANTING DETAILS
L1-115	PLANTING DETAILS
L1-116	PLANTING DETAILS
L1-117	PLANTING DETAILS
L1-118	PLANTING DETAILS
L1-119	PLANTING DETAILS
L1-120	PLANTING DETAILS
L1-121	PLANTING DETAILS
L1-122	PLANTING DETAILS
L1-123	PLANTING DETAILS
L1-124	PLANTING DETAILS
L1-125	PLANTING DETAILS
L1-126	PLANTING DETAILS
L1-127	PLANTING DETAILS
L1-128	PLANTING DETAILS
L1-129	PLANTING DETAILS
L1-130	PLANTING DETAILS
L1-131	PLANTING DETAILS
L1-132	PLANTING DETAILS
L1-133	PLANTING DETAILS
L1-134	PLANTING DETAILS
L1-135	PLANTING DETAILS
L1-136	PLANTING DETAILS
L1-137	PLANTING DETAILS
L1-138	PLANTING DETAILS
L1-139	PLANTING DETAILS
L1-140	PLANTING DETAILS
L1-141	PLANTING DETAILS
L1-142	PLANTING DETAILS
L1-143	PLANTING DETAILS
L1-144	PLANTING DETAILS
L1-145	PLANTING DETAILS
L1-146	PLANTING DETAILS
L1-147	PLANTING DETAILS
L1-148	PLANTING DETAILS
L1-149	PLANTING DETAILS
L1-150	PLANTING DETAILS
L1-151	PLANTING DETAILS
L1-152	PLANTING DETAILS
L1-153	PLANTING DETAILS
L1-154	PLANTING DETAILS
L1-155	PLANTING DETAILS
L1-156	PLANTING DETAILS
L1-157	PLANTING DETAILS
L1-158	PLANTING DETAILS
L1-159	PLANTING DETAILS
L1-160	PLANTING DETAILS
L1-161	PLANTING DETAILS
L1-162	PLANTING DETAILS
L1-163	PLANTING DETAILS
L1-164	PLANTING DETAILS
L1-165	PLANTING DETAILS
L1-166	PLANTING DETAILS
L1-167	PLANTING DETAILS
L1-168	PLANTING DETAILS
L1-169	PLANTING DETAILS
L1-170	PLANTING DETAILS
L1-171	PLANTING DETAILS
L1-172	PLANTING DETAILS
L1-173	PLANTING DETAILS
L1-174	PLANTING DETAILS
L1-175	PLANTING DETAILS
L1-176	PLANTING DETAILS
L1-177	PLANTING DETAILS
L1-178	PLANTING DETAILS
L1-179	PLANTING DETAILS
L1-180	PLANTING DETAILS
L1-181	PLANTING DETAILS
L1-182	PLANTING DETAILS
L1-183	PLANTING DETAILS
L1-184	PLANTING DETAILS
L1-185	PLANTING DETAILS
L1-186	PLANTING DETAILS
L1-187	PLANTING DETAILS
L1-188	PLANTING DETAILS
L1-189	PLANTING DETAILS
L1-190	PLANTING DETAILS
L1-191	PLANTING DETAILS
L1-192	PLANTING DETAILS
L1-193	PLANTING DETAILS
L1-194	PLANTING DETAILS
L1-195	PLANTING DETAILS
L1-196	PLANTING DETAILS
L1-197	PLANTING DETAILS
L1-198	PLANTING DETAILS
L1-199	PLANTING DETAILS
L1-200	PLANTING DETAILS



COURTNEY JANE MILLER
 11111 WILSON AVENUE, SUITE 100
 GARDEN GROVE, CA 92647
 TEL: 714.261.1111
 FAX: 714.261.1112
 WWW.CJM.LA



SANTA BARBARA HUMANE
PHASE 1
 5399 Overpass Road
 Goleta, CA 93111

NOT FOR CONSTRUCTION
SANTA BARBARA HUMANE
PHASE 1
 5399 Overpass Road
 Goleta, CA 93111



PROJECT NUMBER: _____
 DRAWN BY: _____
 DATE DRAWN: _____
 REVISION: _____
 PROJECT DATE: _____
 SCALE: _____
 SHEET NUMBER: _____
 TOTAL SHEETS: _____

Landscaping plan

SANTA BARBARA HUMANE PHASE 2 LANDSCAPE PLANS 5399 OVERPASS ROAD GOLETA, CA 93111



SHEET INDEX

SHEET	DESCRIPTION
PHASE 1 LANDSCAPE SHEETS	
L2 100	TITLE SHEET
L2 101	TREE REMEDIATION PLAN
L2 102	ARBORIST REPORT
L2 103	CONSTRUCTION SITE PLAN, NETS & SCHEDULE
L2 104	FENCE & WALL PLAN
L2 105	LAYOUT PLAN - PHASE 1
L2 106	LAYOUT PLAN - PHASE 2
L2 107	PLANTING NETS & SCHEDULE
L2 108	PLANTING PLAN - PHASE 1
L2 109	PLANTING PLAN - PHASE 2
L2 110	CONSTRUCTION DETAILS - FENCE & GATES
L2 111	PLANNING DETAILS
L2 112	PLANNING PLAN OVERVIEW
L2 113	IRRIGATION PLAN PHASE 1
L2 114	IRRIGATION PLAN PHASE 2
L2 115	IRRIGATION PLAN PHASE 1
L2 116	IRRIGATION PLAN PHASE 2
L2 117	IRRIGATION DETAILS
L2 118	IRRIGATION DETAILS

PHASE 2 LANDSCAPE SHEETS

L2 100	TITLE SHEET
L2 101	TREE REMEDIATION PLAN
L2 102	ARBORIST REPORT
L2 103	CONSTRUCTION SITE PLAN, NETS & SCHEDULE
L2 104	FENCE & WALL PLAN
L2 105	LAYOUT PLAN - PHASE 1
L2 106	LAYOUT PLAN - PHASE 2
L2 107	PLANTING NETS & SCHEDULE
L2 108	PLANTING PLAN - PHASE 1
L2 109	PLANTING PLAN - PHASE 2
L2 110	CONSTRUCTION DETAILS - FENCE & GATES
L2 111	PLANNING DETAILS
L2 112	PLANNING PLAN OVERVIEW
L2 113	IRRIGATION PLAN PHASE 1
L2 114	IRRIGATION PLAN PHASE 2
L2 115	IRRIGATION PLAN PHASE 1
L2 116	IRRIGATION PLAN PHASE 2
L2 117	IRRIGATION DETAILS
L2 118	IRRIGATION DETAILS

PLANNING NOTE
THE SANTA BARBARA HUMANE CAMPUS RENOVATION PROJECT WILL BE CONSTRUCTION PHASE 1 AND PHASE 2. THE COMPLETION OF PHASE 1 IS A PREREQUISITE FOR THE COMPLETION OF PHASE 2. LANDSCAPE FEATURES REFERRED TO IN THESE SHEETS ARE PHASE 2 LANDSCAPE PLANS.

PROJECT CONTACTS

ARCHITECT:
CONTACT: TERRY HARRIS
4425 18TH ST
HARRIS ARCHITECT

OWNER:
CONTACT: MICHAEL HOLLAND
880-823-1111
www.sbh.org

CLIENT:
CONTACT: MARTINE FRENCH, P.E., CCDFP
www.sbh.org

IRRIGATION CONTRACTOR:
CONTACT: STEVE ROSE, ACFI
880-823-1111
www.sbh.org

PHASE 2 SITE STATISTICS
TOTAL GROUND AREA: 1,400,000 SQ. FT.
TOTAL PHASE 2 LANDSCAPE AREA: 1,200,000 SQ. FT.
TOTAL PHASE 2 LANDSCAPE AREA: 1,200,000 SQ. FT.



COURTNEY JANE MILLER
COURTNEY@CJM.LA
COURTNEYJANEMILLER@GMAIL.COM



NOT FOR CONSTRUCTION
SANTA BARBARA HUMANE
PHASE 2
5399 Overpass Road
Goleta, CA 93111




REVISIONS

NO.	DATE	DESCRIPTION

DRAWN BY: _____
DATE DRAWN: _____
SCALE: _____
REVISIONS:
REVISION NUMBER: _____
DATE: _____

Reference solar sizing - 338.5 kWdc total

The solar generation reference profile can be found in the [Aggregated Profiles Spreadsheet](#) and is based off an outdated roof plan. This reference solar system design and generation profile should be used as a running start and proposers should create their own solar system designs based on the updated roof plans shown on slide 12. Also, proposers are recommended to site additional solar if deemed favorable given any landscaping or building proximity conflicts.




SB Humane Solar Segment Size, Generation, and layout details					
Solar Segment	System Size and Annual Generation			System Layout Details	
	Solar System Size (kWdc)	Annual Generation (kWh)	Annual kWh/kWp	JA Solar Module Wattage	Number of Modules
Building A	59.3	98,008	1,653	395	150
Building B	15.4	25,982	1,687	395	39
Building C	75.4	123,868	1,642	395	191
Building D&E	29.6	48,576	1,640	395	75
Building F	10.3	14,935	1,454	395	26
Building I	22.1	36,164	1,635	395	56
Solar Parking Canopy 1 (Northern)	63.2	101,674	1,609	540	117
Solar Parking Canopy 2 (Eastern)	63.2	98,939	1,566	540	117
Totals & Averages	338.5	548,146	1,611	-	771

Site plan with dimensions

APN-071-220-021
 ADJACENT LAND USE:
 GENERAL INDUSTRIAL

APN-071-220-021
 ADJACENT LAND USE:
 GENERAL INDUSTRIAL



Site Plan Keynote Legend


09/G70 2	Accessible Parking Space Sign Post
13/G70 2	Unauthorized Vehicle Parking Signage
401	Electric Enclosure
402	Electric Room
403	Transformer
404	Electric/IT Room/Security Room
405	Fiber Optics Meter Room
406	Main Electric Yard
407	Main Transformer
408	Main 1600 Amp Service Switch Board
410	Main IT/Security Room
411	IT/Security Closet
412	Utility Room
414	Fire Riser
415	Condenser Units
417	Temporary transformer
418	Temporary electrical service
501	Standard parking space, typ.
502	Compact parking space, typ.
503	Accessible parking space, typ.

NOTE: For reference only.
 Work for Solar Canopy to
 be done by others under
 separate permit.

A
DOG ADOPTION CONDITIONED
 6486 SF
DOG ADOPTION UNCONDITIONED
 1481 SF

East solar parking canopy

Site plan with dimensions




APN-071-22
ADJACENT LA
GENERAL IND

Electrical yard (Switchgear, PV controls, BESS, Microgrid Switchgear) and generator sizing & locations

Site plan with major electrical components

Site plan with dimensions



DMHA
ARCHITECTURE + INTERIOR DESIGN

506 Hill 7777
1 N. Calle Cesar Chavez #102
Santa Barbara, CA 93103

Santa Barbara HUMANE

NOT FOR CONSTRUCTION

SB Humane - Campus Renovation
5399 Overpass Road
Goleta, CA 93111


PROJECT # SBCHS1
NO. DESCRIPTION **DATE**

Schematic Design Package	10/20/2020
Final Design	11/10/2020
Final Construction Documents	12/10/2020
Final Construction Documents	12/10/2020
Final Construction Documents	12/10/2020
Final Construction Documents	12/10/2020
Final Construction Documents	12/10/2020
Final Construction Documents	12/10/2020
Final Construction Documents	12/10/2020

AS104.2
PHASE 2 SITE UTILITIES PLAN


Electrical yard with switchgear, PV controls, BESS, & Microgrid Switchgear, and transformer dimensions

Site plan with dimensions




BESS datasheet

The reference BESS is a Tesla 326 kW & 1,305 kWh configuration can fit into the dimensions shown below and can be enclosed within a moveable fence for installation and servicing needs.



SB Humane - Battery Energy Storage Sizing and Resilience					
Critical Load Profile Peak Demand (kW)	Solar System Size Year 1 (kW)	Recommended Battery System Size (Year 1)		Indefinite Resilience (Critical Load Profile)	
		Standard Option Battery Power Capacity (kW)	Standard Option Battery Energy Capacity (kWh)	Total Percentage of Critical Load Kept Online Indefinitely (Year 1)	Total Percentage of Critical Load Kept Online Indefinitely (Year 15)
256	339	326	1,305	27%	24%

Site plan with dimensions



ENLARGED BACK-UP GENERATOR 02
1/4" = 1'-0"

Generator & controller datasheets

- The diesel generator plan-of-record is a 350 kW Generac MD350 with DeepSea 8610 MKII genset controller, with 946 gallons of usable capacity, and Level 2 acoustic enclosure.
- The generator should be configured to operate in only three possible modes:
 1. Charging the Battery Energy Storage System (BESS) to full when the BESS state-of-charge (SOC) hits 10% and then turn off until the same 10% SOC condition is reached again. While charging the BESS, the generator should operate at its optimized nameplate capacity.
 2. While the diesel generator is run for maintenance purposes, it should charge the BESS (there should be no added equipment, e.g. a load bank, required for maintenance runs).
 3. If the Solar Microgrid is non-functional for any reason, the diesel generator must be able to backup the SB Humane site.

DSE8610 MKII SYNCHRONISING & LOAD SHARING AUTO START CONTROL MODULE



MD350 | 12.9L | 350 kW
INDUSTRIAL DIESEL GENERATOR SET
EPA Certified Stationary Emergency

GENERAC INDUSTRIAL
POWER

Standby Power Rating
350 kW, 438 kVA, 60 Hz

Prime Power Rating*
315 kW, 394 kVA, 60 Hz



*EPA Certified Prime ratings are not available in the US or its Territories





Image used for illustration purposes only

Solar Microgrid load management and sequence-of-operations (SOO)


In the case of the **SB Humane** sites, **two load groups are defined:**

- **Tier 1: Buildings A, C, F, and H.** These buildings should remain powered through a grid outage.
- Tier 2: There are no Tier 2 loads.
- **Tier 3: Buildings B, D, E, G, and I, and all electric vehicle charging infrastructure (EVCI).** These buildings will be completely unpowered by default in island mode but can optionally be independently powered when excess solar generation is available.



At the SB Humane campus, load management is **by building**. Five buildings and two EV charging circuits are non-critical and will be disconnected in island mode. The four critical buildings will remain fully powered; they do not have smart critical load panels and should operate normally throughout grid outages.

The microgrid controller is responsible for controlling shunt-trip breakers for load management.



EV Charging Infrastructure at SB Humane


Site plan with dimensions

Two solar parking canopies (along the north and east of the site) will have 11 EV charging ports each, for a **total of 22 EV charging ports**.

Sykra carries responsibility for the breakers, transformers, trenching, and wiring all the way to stub-outs at the two EV charging locations.

The **Designer-Building-Owner-Operator (DBOO)** is responsible for selecting and installing the **EV charging stations** and ensuring that the stations meet Solar Microgrid operational requirements, specifically:

- 1) Toggling the EVCI breakers at the switchgear
- 2) Controlling individual EV charging station



The SB Humane solar microgrid, by a SOO load service via dispatch of the solar, BESS, and fossil fuel generator (FFG). The SOO includes four principal steps:


1) Normal Operations, Grid Connected

2) Grid to Island Transition, in which the battery seamlessly assumes grid-forming for just the critical buildings, while all other circuits toggled off.

3) Island Operation

- 3a) Stable island operation, in which solar generation is maximized and FFG operating time is minimized.
- 3b) If there is surplus solar generation, Tier 2 & Tier 3 load circuits can be toggled on.
- 3c) If BESS SOC falls below a threshold, the diesel generator (diesel generator operates at nameplate for the minimum time to charge the BESS).
- 3d) If the Solar Microgrid is non-operational, the diesel generator must act as the grid-forming master. Ie, the diesel generator must be configured to function as a backup to the backup.

4) Grid Resynchronization, in which the microgrid controller executes a seamless transition back to grid-connected mode.




FFG (diesel generator) operates as “backup to the backup”

Electrical single-line diagram

ES004.2: Electrical single-line diagram (Syska)

Load management via shunt-trip breakers



ES004.2
Sheet
Keynote #1
requires
separate
microgrid
switchgear


Electrical Single-Line Diagram

The “by others” sheet keynote in E004 implies that the Designer, Builder, Owner, Operator (DBOO) for the Solar Microgrid has design responsibility for a separate microgrid switchgear cabinet with integrates the BESS, diesel generator, and PV generation (likely through a separate PV combiner panel).

The DBOO must assume design responsibility for the dedicated microgrid switchgear, including **“stamping” of final project drawings**. DBOOs must be fully aware of this design responsibility.

Although it may be desirable to integrate the BESS, diesel generator, and PV generation directly into the main switchgear, such an integrated design is not allowed due to contractual limitations. RFP respondents should plan for a dedicated microgrid switchgear cabinet.

Breaker marks separation of responsibilities




SM Electrical (DBOO)

Non-SM Electrical (Syska)

Reference Solar Microgrid design

Reference Solar Microgrid single-line diagram

Reference electrical single-line diagram and key data sheets



- ### SHEET NOTES
- 1800A SA CTs AND 4:1 PTs PER PHASE. ROUTE IN 1" C W/ COMMS AND CONTROLS CABLES
 - CONNECT TO EXISTING CIRCUIT BREAKER BY OTHERS. (PREVIOUS PROJECT PHASE)
 - 200A 480V CONTACTOR WITH 120VAC N.O. CLOSE COIL IN NEMA 3R ENCLOSURE
 - INSTALL NEW EMERSON RST-EP MICROBUS ADAPTER-EPVMS001 OUTPUT-EP-2714 (4x F00M C) INPUT-EP 1214 (4x INPUTS)
 - INSTALL NEW SEL-735 METER ph 0735B20924EXXXXX16101XX 1800SA CTs
 - INSTALL 4:1 PTs PER PHASE FOR METERING AND PROTECTION. SEE E-103 FOR ADDITIONAL DETAILS.
 - INSTALL NEW SEL-700G RELAY ph 0700G20CBOX7 4803001 PROVIDE 12AWG F00R CB CONTROL AND MONITORING
 - INSTALL NEW SEL-735 METER ph 0735B20924EXXXXX16101XX 300SA CTs
 - INSTALL NEW SEL-735 METER ph 0735B20924EXXXXX16101XX 600SA CTs
 - PROVIDE 120VAC PRIMARY POWER AND 24VDC UPS POWER TO TSC
 - NEW 35kW SYNCHRONIZING GENERATOR WITH DEEP SEA DSE 8010 MKII GENERATOR CONTROLLER
 - GROUNDING TRANSFORMER REQUIRED BY TESLA FOR GRID FORMING- TESLA TO PROVIDE SIZING INFORMATION
 - 12AWG TWISTED PAIR IN 1" FROM GND TX CIRCUIT BREAKER N.O. CONTACT TO MP2 XL REMOTE SHUTDOWN TERMINALS

SYSTEM TOTALS

PV SYSTEM	
11x SMA STP & CORE1 Inverters	346.5kW / 338.4kW @ 480Vac, 3ph, 771 PV Panels
BESS SYSTEM	
Tesla Megapack 2 XL	500kW / 500kVA, 2011kWh (4-hr), ph 1T 480V-208A
Tesla System Controller	Integrated Fusing, Integrated Cell Modern w/Antenna, Includes Hardware RPS20 LANZ Switch, ph 1052303-02-G
GENERATOR	
Genpac-MD300 in enclosure	35kW / 38kVA
Generator Controller	Deep Sea DSE 8610 MKII

— NEW
— EXISTING

SBHS Microgrid
5399 Overpass Road
Gonza, CA 93111

Santa Barbara HUMAN
Drawing by EFM

SINGLE LINE DIAGRAM

Microgrid components (PV combiner, BESS, and diesel generator) come together at a dedicated microgrid switchgear cabinet, then connect to the main site switchgear via a single breaker.

Revision	Date
75% CD	2023-10-09
75% CD-r1	2023-10-10

E-101

Project schedule

- **29 Dec 2023 – 29 Mar 2024**: Solar Microgrid RFP Process and Selection of Microgrid Design/Build Contractor
- **01 Apr 2024 – 28 June 2024**: Microgrid Construction Permit Documents (Phase 2)
- **01 Jul 2024**: City of Goleta Building Department Solar Microgrid Plan Change Submittal (Phase 2)
- **12 Jul 2024 to 01 Aug 2024**: City of Goleta Building Department Re-submittal (2) & Permit Approval (Phase 2)
- **02 Aug 2024**: Building Permit Approved – (Phase 2)
- **02 Aug 2024 to 22 Aug 2024**: Review & Respond to Plan Check Comments (3) – (Phase 2)
- **15 Aug 2024 to 04 Sep 2024**: Selection of GC and Finalized Contract – (Phase 1 & Phase 2)
- **23 Aug 2024 to 06 Sep 2024**: City of Goleta Building Department Re-submittal (3) & Permit Approval – (Phase 2)
- **06 Sep 2024**: Building Permit Approved – (Phase 2)
- **06 Sep 2024**: Construction Buy Out – (Phase 1 & Phase 2)
- **09 Sep 2024 to 18 Oct 2024**: Procurement – (Phase 1)
- **09 Sep 2024 to 30 Sep 2024**: Client Review & Approval for Construction to Begin – (Phase 1)
- **04 Oct 2024**: Pre-Construction Meeting – (Phase 1)
- **21 Oct 2024**: Start Construction – (Phase 1)
- **21 Oct 2024 to 19 Dec 2025**: Assume 14 months for demo, site work and construction (Phase 1)
- **15 Sep 2025 to 19 Dec 2025**: Procurement – (Phase 2)
- **08 Dec 2025**: Pre-Construction Meeting – (Phase 2)
- **22 Dec 2025**: Start Construction – (Phase 2)
- **22 Dec 2025 to 12 Nov 2027**: Assume 22 months for demo, site work and construction (Phase 2)

PPA pricing requirements

- Complete system cost: solar, storage, all components, installation to operational.
- PPA price: \$/kWh, 25 years, must be fixed with no escalation.
- Provide PPA price increment for each \$100K of potential system cost increase.
- PPA payments are the only source of revenue for PPA Holders – unless future grid services offer mutually agreed revenue-share opportunities.
- Provide numeric buy-out values for year-end 10, 15, 20 and 25 years.
- SB Humane is retaining all environmental attributes.
- The minimum storage energy capacity available for daily cycling must be specified, as this significantly effects the economic benefits of the storage.
- The anticipated storage replacement and/or augmentation strategy must be specified in order to ensure the minimum storage capacity available for daily cycling can be maintained for the full 25-year duration.
- Storage and load management solutions can optimize economics via demand charge management & arbitrage.
- Data access showing real-time and historic performance of all Solar Microgrids and allowing easy load management control, including for real-time load management changes, must be specified in final proposals.
- SB Humane has operational control to toggle Tier 3 loads remotely when there is excess energy available in island mode. Excess energy means energy beyond real-time Tier 1 loads.

[Pricing requirements should be reflected in the pricing spreadsheets here](#)